Comparative Statement

Tender Number	BBMP/2018-19/OW/WORK_INDENT32618
Tender Name	Filling potholes in main road and cross roads in Dasarahalli in ward no 15

SNo	Item Name	Unit	Estimate Quantity	Estimate Rate	Total Amount	RAGHUNAANDAN LINGAIAH (LINGAIAH RAGHUNANDAN)		G N RAMESH (G N RAMESH)	
						Quoted Rate	Total Amount	Quoted Rate	Total Amount
1	Providing, laying, spreading and compacting crushed stone aggregates of granite / trap / basalt to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications and as per the direction of Engineer-in-charge of the work..	Cum	221.2	2001.28	442683.136	2241.43	495804.316	2251.44	498018.528
2	Filling Pot-holes and patch repairs with bituminous concrete, 40 mm, KSRRB M3000-5, Removal of all failed material, trimming of completed excavation to provide firm vertical faces, cleaning of surface, painting of tack coat on the sides and base of excavation as per clause 500.3 back filling the pot hole with bituminous material as per clause 500.4 compacting, trimming and finishing the surface to form a smooth continuous surface, all as per clause 3004.2 complete asspecifications and as per the direction of Engineer-in-charge of the work.	Sqm	1106	365.7	404464.20	409.58	452995.48	411.41	455019.46
	Total Summary Amount				847147.34	948799.80		953037.99	
	% against Estimated Rate					11.9994		12.4997	
	% against CSR								
	Total Bid Amount					948799.80 (L1)		953037.99 (L2)	

The rate quoted by contractor Sri RAGHUNAANDAN LINGAIAH is (+)11.99% Above of Rs 948799.00 on S.R. 2018-19

Executive Engineer
Dasarahalli Division
BBMP